

Bid Addendum

Contract No.	N/A	Project No.	12669030
Bid Addendum No.	01	Date Issued	July 20, 2026
Owner	McKinleyville Community Services District		
Consultant	GHD		
Project	Highway Sewer Crossing Retrofit		

The purpose of this Addendum is to modify the Contract Documents for the subject project. This Addendum, including attachments, shall become part of said Contract Documents. Each bidder shall acknowledge receipt of this addendum in their bid proposal.

1. The Following Items Provide Changes to the Plans:

None.

2. The Following Items Provide Changes to the Specifications:

Cultural Monitoring will be provided by the District and is therefore removed from the Contract. This change is addressed in Items 2.1 and 2.2 below. Item 2.2 also addresses bid item cross referencing errors.

Item 2.1: REPLACE Bid Requirements, South Crossing Bid Schedule, Page 1-12, with the attached revised version dated 7/13/2026.

Item 2.2: REPLACE Specification Section 01 15 00 Measurement and Payment in its entirety with the attached revised version dated 7/13/2026.

3. The Following Items Provide Responses to Bidder Questions:

Item 3.1:

Question: *Can you please provide the Plan Holder Lists?*

Response: See attached Owner Planholders List.

4. The Following Items Provide Clarifications to the Contract:

Item 4.1: The engineer's opinion of probable construction cost will be available after bid opening.

Attachments:

1. Bid Requirements, South Crossing Bid Schedule, Page 1-12, dated 7/13/2026.
2. Specification Section 01 15 00 Measurement and Payment, dated 7/13/2026.
3. Planholders List, dated 7/13/2026.

END OF ADDENDUM

Issued By:

GHD

Patrick Sullivan

Print Name



Sign

Date: 7/20/2026

BASE BID SCHEDULE – MIDDLE CROSSING					
2.16	Existing 48-inch Sewer Manhole Rehabilitation (MH5-2, MH5-3)	EA	2	\$ _____	\$ _____
2.17	New Sewer Manhole Interior Coating (MH5-2-1, MH5-4-1, and MH5-4-2)	EA	3	\$ _____	\$ _____
2.18	Final Paving, Curb and Gutter Replacement on Thiel Avenue	LS	1	\$ _____	\$ _____
2.19	Settlement Monitoring	LS	1	\$ _____	\$ _____
2.20	Replace Fence	LS	1	\$ _____	\$ _____
2.21	Landscape Restoration	LS	1	\$ _____	\$ _____

MIDDLE CROSSING SUBTOTAL (\$ _____)

MIDDLE CROSSING SUBTOTAL IN WORDS: _____

Item 3. South Crossing Bid Schedule:

BID SCHEDULE – SOUTH CROSSING					
Item No.	Description	Unit	Qty	Unit Cost	Total Cost
3.01	Work Area Mobilization/Demobilization	LS	1	\$ _____	\$ _____
3.02	Construction Staking	LS	1	\$ _____	\$ _____
3.03	Traffic Control	LS	1	\$ _____	\$ _____
3.04	Erosion and Sediment Controls	LS	1	\$ _____	\$ _____
3.05	Cultural Monitoring (NOT IN CONTRACT)				
3.06	Potholing	LS	1	\$ _____	\$ _____

SECTION 01 15 00

MEASUREMENT AND PAYMENT

PART 1 GENERAL

1.1 SUMMARY

- A. Section Includes:
 - 1. General.
 - 2. Work Included Under All Bid Items.
 - 3. Bid Schedules

1.2 GENERAL

- A. Unless otherwise specified in other individual sections of these Specifications, quantities of Work will be determined from measurements or dimensions in horizontal planes.
- B. Units of measurement will be in accordance with U.S. Standard Measures.
- C. See Article 6 of the General Conditions for special provisions related to Contract Modification Procedures.
- D. See Article 8 of the General Conditions for special provisions related to Schedule of Values and Progress Payments.
- E. Lump Sum Bid Price
 - 1. Payment for the lump sum bid price will include all compensation to be received by the Contractor for furnishing all material, tools, equipment, supplies, and manufactured articles, and for all labor, operations, and incidentals appurtenant to the items of work being described, as necessary to complete the various items of work all in accordance with the requirements of the Contract Documents, including all appurtenances thereto, and including all costs of permits and cost of compliance with the regulations of public agencies having jurisdiction, including Safety and Health Requirements of the California Division of Industrial Safety and the Occupational Safety and Health Administration of the U.S Department of Labor (OSHA).

1.3 WORK INCLUDED UNDER ALL BID ITEMS

- A. Contractor shall ensure each of the following is included as part of the work under each bid item:
- B. The safety of personnel, subcontractor's personnel, and the public. Safety measures shall include, but are not limited to, shoring, confined space entry, abrasive blasting, fall protection, electrical safety and warning signs as may be necessary. Safety measures shall comply with applicable laws, regulations, permits, and the Contract Documents.

- C. All bid items related to the demolition or installation of underground elements such as underground pipelines and appurtenances shall include, but not be limited to: potholing to identify utility locations and conflicts, initial and final saw cutting, excavation and disposal of trench section materials including pavements, soils, and preservation of existing items, pipe bedding and backfill, pipe, joints, and other fittings as required, tracer wire, installation above or below existing utilities, supporting exposed utilities and pipes, repair or replacement of damaged existing utilities, handling and disposal of asbestos cement pipe, trench plating, trench shoring and safety, control of grades, survey construction staking, protection of trees and roots, aggregate base, temporary and final trench paving, adjusting new and existing utility rims and covers to finish grade, testing, and all other related work as described in the Contract Documents.
- D. Make available all work for inspection and/or testing by the Engineer.
- E. Clearing, pruning, and removal of vegetation or site features shall be performed only where shown on the Contract Drawings and as required by applicable permits. Measurement and payment shall be included in the applicable bid items unless specifically identified otherwise.
- F. Restore all surfaces to their original, existing condition as nearly as possible including landscaping, sidewalks, pavement, and curbs and gutters. All materials for restoration work shall be furnished by contractor.
- G. Trees not identified for removal shall be protected.
- H. Proper removal and disposal of existing abandoned utilities or other subsurface structures as required to complete construction of the work.
- I. Proper restraint of existing facilities. Temporary restraints may be necessary to prevent facilities from being damaged. Damage to existing facilities that occurs due to improper restraint shall be repaired by Contractor at his own expense.
- J. Miscellaneous site demolition as required for the various bid items.
- K. Disposal of all excess or waste materials.
- L. Cleanup and sweeping of the project access roads of tracked dirt and debris.
- M. Quality control. The Contractor is responsible for providing independent third-party quality control for all on-site phases of the project.
- N. Provide advance notice of road or lane closures.
- O. Noise and sound control.
- P. Startup, testing, and commissioning.
- Q. Submittals for the project.

- R. As-built drawings. No portion of the work shall be deemed complete unless reflected on the as-built drawings. Contractor shall always maintain an active set of as-built drawings on site. At the completion of work, the Contractor shall provide as-built drawings to the Owner as a record of work completed.

1.4 BID SCHEDULE

- A. The bid item measurement and payment descriptions are generally the same between the Middle Crossing and South Crossing work areas, unless noted otherwise, while the extent, nature, or quantity of work may vary between locations where noted in this section, in the Specifications, and as shown on the Contract Drawings.
- B. The Owner reserves the right to award one, any combination, or all of the Work Area Bid Schedules listed below:
 - 1. Middle Crossing Work Area
 - 2. South Crossing Work Area
- C. Each Work Area Bid Schedule constitutes an independent and complete base scope of work, capable of being awarded and constructed on a standalone basis. If fewer than all Work Area Schedules are awarded, the Owner will select which Work Area Schedule(s) to award based on Owner priorities. The selection of awarded Work Area Schedule(s) is independent of construction sequencing and independent of bid item numbering.
- D. Mobilization/Demobilization is covered in two different bid item categories as outlined below and as described in the bid item measurement and payment descriptions:
 - 1. Major Equipment Mobilization/Demobilization.
 - a. This item only covers transportation of major equipment onto and off of the project site. This item shall be awarded if one or more Work Areas are awarded.
 - 2. Work Area Mobilization/Demobilization.
 - a. This item covers standard Mobilization/Demobilization work items but excludes major equipment transport. This item is awarded when the corresponding Work Area is awarded.

ITEM 1 – MAJOR EQUIPMENT MOBILIZATION/DEMobilIZATION

Item 1.01 – Major Equipment Mobilization/Demobilization

Payment for this item shall be on a lump sum basis. Measurement shall correspond to percent complete as confirmed by the Engineer. Payment shall include full compensation for mobilizing major equipment to the project site as well as demobilization of the same for the construction of the project. Major equipment includes specialty HAB equipment and excavators. Minor equipment includes all other equipment needed to perform the work.

All other standard mobilization and demobilization work is covered under the Work Area Mobilization/Demobilization bid items including setting up major equipment after the equipment has been mobilized and tearing down the equipment in preparation of demobilization.

When 10 percent of the total original Contract amount is earned from bid items, excluding amounts paid for materials on hand, 90 percent of the amount of the bid price for mobilization, or 10 percent of the total Contract amount, whichever is least, will be paid for mobilization. Upon completion of all Work on the project, payment of the balance of the bid amount for Major Equipment Mobilization/Demobilization will be paid.

ITEM 2 – MIDDLE CROSSING WORK AREA

Item 2.01 – Work Area Mobilization/Demobilization

Payment for this item shall be on a lump sum basis per the amount listed for this item in the Bid Schedule. Measurement shall correspond to percent complete as confirmed by the Engineer. Payment shall include full compensation for mobilizing minor equipment, materials, and labor to the project site as well as demobilization of the same for the construction of the project. Items covered by this include, but are not limited to, bonds, insurance, contracting and administrative costs, permitting and permit compliance costs, costs associated with temporary facilities and utilities, punch list items, repairs of damaged property, repairs to damaged utilities, site cleanup, and project maintenance and warranty.

This item excludes mobilization and demobilization of major equipment which is covered under Bid Item 1.01.

When 10 percent of this Work Area contract amount is earned from the bid items, excluding amounts paid for materials on hand, 90 percent of the amount of the bid price for mobilization, or 10 percent of the Work Area Contract amount, whichever is least, will be paid for mobilization. Upon completion of all Work on the project, payment of the balance of the bid amount for mobilization/demobilization will be paid.

Item 2.02 – Construction Staking

Measurement for this item shall be on a lump sum basis. Payment shall include full compensation for all materials, labor, equipment, and supervision necessary to perform construction staking as required to lay out and complete the work shown on the Contract Drawings and specified in the project documents. This includes, but is not limited to, staking for alignments, structures, manholes, and other construction features; verifying installation of improvements; and furnishing all necessary survey control, materials, and documentation. No additional payment is provided for incidental staking or re-staking due to Contractor operations.

Item 2.03 – Traffic Control

Payment for this item shall be on a lump sum basis per the amount listed for that item in the Bid Schedule. Measurement shall correspond to percent complete as confirmed by the Engineer. Payment shall include full compensation for providing traffic control as described in the Drawings, in these Specifications, and as required by the Humboldt County and Caltrans Encroachment Permits (draft Encroachment Permits are included as Appendices to these Specifications, final permits shall be obtained by Contractor). Items covered by this item include, but are not limited to, labor, materials, equipment, and other expenses for complete traffic control throughout the length of the project including times when the Contractor is not working on site. Items covered by this include but are not limited to finalizing the Humboldt County and Caltrans Encroachment Permits, development and implementation of an approved traffic control plan, notifications, road detours, signage, lighting, flaggers, temporary pavement delineation, barricades, plating, K-Rail, and all other materials and equipment needed to temporarily control traffic.

throughout the project.

Item 2.04 – Erosion and Sediment Controls

Measurement for this item shall be on a lump sum basis. Payment shall include full compensation for all materials, labor, equipment, and supervision necessary to prepare and submit a Storm Water Pollution Prevention Plan (SWPPP); and construct and maintain water pollution control best management practices as required by the Regional Water Quality Control Board's NPDES. This Work covers all Contractor costs and effort associated with providing permits and water pollution control measures including, but not limited to, erosion and sediment control measures such as silt fences, fiber rolls, and diversion dikes. Work under this item shall be paid based on the overall percent completion of the project.

Item 2.05 – Potholing

Measurement for this item shall be on a lump sum basis. Payment shall include full compensation for all materials, labor, equipment, and supervision necessary to locate existing underground utilities and to locate all connection locations. Potholing shall be used to identify size, material, depth, utility type and other characteristics and features necessary to properly complete the work. Contractor shall employ other utility locating techniques for convenience and shall confirm all locations through potholing as required under this item. Under this bid item, the Contractor shall confirm via potholing the necessary size and type of fittings and couplers required for all interconnections prior to attempting to make such connections and the cost of such fittings and couplers is included under other bid items. Contractor shall provide redlines to Owner prior to proceeding with the improvements work. Items covered by this bid item include, but are not limited to, identification of potholing locations, utility marking and coordination with utility owners to schedule utility marking, potholing, surveying of utility locations identified and further data gathering and documentation, verification of required fittings and couplers, restoration of potholing locations, and repair of utilities and other features damaged during potholing.

Item 2.06 – Demolition

Measurement for this item shall be based on a lump sum basis. Payment shall include full compensation for all materials, labor, equipment, and supervision necessary for the removal and disposal of vegetation, trees, manholes, and sewer mains, and other demolition work for other Bid Items. Work includes, but is not limited to, clearing and grubbing, vegetation trimming, tree removal, disposal, manhole demolition, sewer main demolition and abandonment, disposal, pavement removal, excess soils, and other miscellaneous demolition items not otherwise included in other Bid Items, as shown on the Design Drawings. Removal of trees will consist of clearing logs, branches, limbs and brush and the area to be swept clean of all tree debris after completion of work on site. Work areas shall be left in a "lawn raked clean" condition upon completion of each day. Payment shall also include full compensation for all materials, labor, equipment, and supervision necessary to obtain necessary permits and pay hauling and disposal fees as shown on the Design Drawings and as required by the Specifications.

Item 2.07 – Temporary Bypass Pumping

Measurement for this item shall be on a lump sum basis. Measurement shall correspond to percent complete as confirmed by the Engineer. Payment shall include full compensation for all materials, labor, equipment, and supervision necessary to install and maintain temporary bypass pumping facilities for the sanitary sewer collection system throughout the length of the project including times when the Contractor is not working on

site. This item also includes the removal of temporary pumping and restoration of pavement, sidewalks, and other areas. The Contractor shall develop and submit a bypass pumping plan for Engineer approval based on Contractor proposed construction schedule and sequencing.

Item 2.08 – Dewatering

Measurement for this item shall be on a lump sum basis. Payment shall include full compensation for all materials, labor, equipment, and supervision necessary for dewatering the trenches, pits, and excavations to perform the Work. Items covered by this include, but are not limited to, dewatering pumps, wells, piping and hoses, filtration devices, tanks, electrical power, dewatering disposal, and all other required items for a functional dewatering system.

Item 2.09 – Middle Sewer Crossing via HAB – 12-inch Carrier Pipe in Steel Casing

Measurement for this item shall be on a lump sum basis. Payment shall include full compensation for materials, labor, equipment, and supervision necessary for trenchless drilling the 12-inch sewer main within a steel casing under Highway US-101 via Horizontal Auger Boring via a unguided or guided system, as shown on the Contract Drawings and described in the Specifications including Section 33 05 07.22 Part 1.4 H. Items covered include, but are not limited to, excavation to protect existing drainage ditch, bracing, controls, carrier piping, casings, fittings, and connections at both ends, welding, jacking and receiving shafts, drilling pad, using temporary fill, timber mats or steel plates, removal of excess materials, sheeting, shoring and bracing, site repair, and all other related work per the Contract Documents.

Item 2.10 – Sewer Manhole 60-inch Diameter (MH5-2-1 and MH5-4-1)

Measurement for this item shall be on a per unit basis. Payment shall include full compensation for all equipment, labor, materials and incidentals required for construction of 60-inch diameter sewer manhole, including but not limited to, sawcutting, pavement removal and disposal, trenching, disposal of native soils, imported backfill, compaction, temporary paving, factory cast monolithic base, precast manhole sections, interior coating, and joint wrap system, manhole frame and cover; connections to new and existing sanitary sewers, acceptance testing, and all appurtenant work, complete and in place as shown in the drawings and as required in the specifications.

Item 2.11 – Sewer Manhole 72-inch Diameter (MH5-4-2)

Measurement and payment for this item shall be similar to Base Bid Item 2.10 but is for a 72-inch diameter sewer manhole with a drop inlet connection.

Item 2.12 – Sewer Main 10-inch PVC

Measurement for this item shall be on a linear foot basis. Payment shall include full compensation for all materials, labor, equipment, and supervision necessary to provide planning, execution, acceptance testing, and management of the completion of all work associated with installation of 10-inch SDR35 PVC sewer piping and associated fittings as shown on the plans and as required in the specifications. Work includes confirmation of the necessary size and type of fittings and couplers required for all interconnections and providing and installing such fittings, layout, sawcutting/demolition and removal of pavement and concrete, excavation, spoils disposal, control of grade, control of water, bedding, piping, backfill material and backfilling, compaction, compaction testing. The Contractor will be required to navigate around existing crossing utilities including, but not necessarily limited to, gas lines, water lines, electrical lines, communication lines, and

storm drains, and will be required to support existing utilities and backfill excavations per the requirements in the Drawings and Specifications.

Item 2.13 – Sewer Main 12-inch PVC

Measurement and payment for this item shall be similar to Base Bid Item 2.12 but is for a 12-inch main.

Item 2.14 – Connect to Existing Sewer Main

Measurement for this item shall be on a per unit basis. Payment shall include full compensation for all materials, labor, equipment, and supervision necessary to connect new sewer mains to existing sewer mains with new sewer couplings. Work related to excavation, backfill, and testing of the connections on the sewer mains is covered under the Sewer Main bid items for which this Work applies.

Item 2.15 – Connect to Existing Sewer Manhole and Rechannel (MH5-2)

Measurement for this item shall be on a per unit basis. Payment shall include full compensation for all materials, labor, equipment, and supervision necessary to connect new sewer mains to existing sewer manholes. Work includes but is not limited to, concrete coring, connecting sewer mains to manholes, removing existing channel and rechanneling manholes, sealing new manhole connection, and manhole testing.

Item 2.16 – Existing Sewer Manhole Rehabilitation (MH5-2, MH5-3)

Measurement for this item shall be on a unit basis for each sewer manhole rehabilitated. Payment shall include full compensation for furnishing all materials, labor, equipment and supervision necessary to install the rehabilitation coating system, complete and in place for all manholes identified on the Plans and Specifications. The work includes, but is not limited to, pre-rehabilitation cleaning and disposal of materials, surface repairs, surface restoration, cleanup, and manhole testing.

Item 2.17 – New Sewer Manhole Interior Coating (MH5-2-1, MH5-4-1, and MH5-4-2)

Measurement and payment for this item shall be similar to Base Bid Item 2.16 but is for new manholes.

Item 2.18 – Final Paving, Curb and Gutter Replacement on Thiel Avenue

Measurement for this item will be on a lump sum basis. Payment shall include full compensation for all materials, labor, testing, equipment, disposal, and other materials and work necessary to provide new pavement and restore pavement, concrete, and curb and gutter where disturbed as shown on the Contract Documents and as may be required to restore areas affected by construction activities. This bid item includes survey and layout, excavation, removal and disposal of unsuitable materials, importation and installation of subgrade materials, grade control, compaction and compaction testing, providing and installing concrete and asphalt, restoration of striping and other pavement markings and signage, and all other work associated with new and restored pavement and concrete. This bid item includes pavement restoration for utility trench work. This bid item also includes repair to pavement and concrete damaged during the course of construction. Work related to pavement demolition is covered under the item for which the demolition occurs.

Item 2.19 – Settlement Monitoring

Measurement for this item shall be on a lump sum basis. Payment shall include full compensation for all materials, labor, equipment, and supervision necessary to furnish and

install settlement monitoring points at locations shown on the Drawings and as required by the Caltrans Encroachment Permit, perform baseline readings prior to construction, conduct regular monitoring during trenchless operations and post-installation as specified in Section 31 09 13, record and report all measurements including any deviations beyond allowable tolerances, and maintain monitoring equipment and accuracy throughout the monitoring period. No additional payment for work required to maintain accuracy or repeat measurements due to Contractor error.

Item 2.20 – Replace Fence

Measurement for this item shall be on a lump sum basis. Payment shall include full compensation for all materials, labor, equipment, and supervision necessary to remove and replace existing fencing in kind or as shown in the Contract Drawings and as required to perform the Work. Work includes, but is not limited to, existing fence removal, in kind fence replacement, excavation, new fencing, and concrete footings.

Item 2.21 – Landscape Restoration

Measurement for this item shall be on a lump sum basis. Payment shall include full compensation for all materials, labor, equipment, and supervision necessary to restore the site to preconstruction conditions required by the Contract Drawings and Specifications, including restoring disturbed areas, providing replacement topsoil as needed, restoration of pavement and access routes, application of seed, straw, hydroseeding, or other specified revegetation methods to all disturbed vegetated areas, restoration of landscaping, fencing, and other site features to pre-construction conditions or as shown on the plans, removal and proper disposal of unsuitable soils, debris, and excess materials, and final cleanup and sweeping of the project site.

ITEM 3 – SOUTH CROSSING WORK AREA

Item 3.01 – Work Area Mobilization/Demobilization

Measurement and payment for this item shall be similar to Base Bid Item 2.01.

Item 3.02 – Construction Staking

Measurement and payment for this item shall be similar to Base Bid Item 2.02.

Item 3.03 – Traffic Control

Measurement and payment for this item shall be similar to Base Bid Item 2.03.

Item 3.04 – Erosion and Sediment Controls

Measurement and payment for this item shall be similar to Base Bid Item 2.04.

Item 3.05 – Cultural Monitoring (NOT IN CONTRACT)

Not used.

Item 3.06 – Potholing

Measurement and payment for this item shall be similar to Base Bid Item 2.05.

Item 3.07 – Demolition

Measurement and payment for this item shall be similar to Base Bid Item 2.06.

Item 3.08 – Temporary Bypass Pumping

Measurement and payment for this item shall be similar to Base Bid Item 2.07.

Item 3.09 – Dewatering

Measurement and payment for this item shall be similar to Base Bid Item 2.08.

Item 3.10 – South Sewer Crossing via HAB – 18-inch Carrier Pipe in Steel Casing

Measurement and payment for this item shall be similar to Base Bid Item 2.09 but is for an 18-inch carrier pipe.

Item 3.11 – Steel Casing Cathodic Protection

Measurement for this item shall be on a lump sum basis. Payment shall include full compensation for furnishing all labor, materials, equipment, coordination, and supervision necessary to provide a complete and functional cathodic protection system as shown on the Contract Drawings and specified in the project documents. Work includes, but is not limited to, installation of anodes including excavation as necessary; trenching and placement and connection of lead wires, connectors, and attachments; installation of test stations; vaults; excavation, backfill, retention of a Certified Cathodic Protection Specialist to oversee completed testing and verification of system operation; completion of all incidental work required to install the system; re-testing and repair if necessary; and site restoration and clean up.

Item 3.12 – Sewer Manhole 60-inch Diameter (MH3-9-1, MH3-10-1, and MH3-10-2)

Measurement and payment for this item shall be similar to Base Bid Item 2.10.

Item 3.13 – Sewer Main 15-inch PVC

Measurement and payment for this item shall be similar to Base Bid Item 2.12 but is for a 15-inch main.

Item 3.14 – Sewer Main 18-inch PVC

Measurement and payment for this item shall be similar to Base Bid Item 2.12 but is for an 18-inch main.

Item 3.15 – Connect to Existing Sewer Main

Measurement and payment for this item shall be similar to Base Bid Item 2.14.

Item 3.16 – Connect to Existing Manhole and Rechannel (MH3-9)

Measurement and payment for this item shall be similar to Base Bid Item 2.15.

Item 3.17 – Existing Sewer Manhole Rehabilitation (MH3-9)

Measurement and payment for this item shall be similar to Base Bid Item 2.16.

Item 3.18 – New Sewer Manhole Interior Coating (MH3-9-1, MH3-10-1, and MH3-10-2)

Measurement and payment for this item shall be similar to Base Bid Item 2.17.

Item 3.19 – Settlement Monitoring

Measurement and payment for this item shall be similar to Base Bid Item 2.19.

Item 3.20 – Replace Fence

Measurement and payment for this item shall be similar to Base Bid Item 2.20.

Item 3.21 – Landscape Restoration

Measurement and payment for this item shall be similar to Base Bid Item 2.21.

END OF SECTION

Planholders List

Contract No.	N/A	Project No.	12669030
---------------------	-----	--------------------	----------

Owner	McKinleyville Community Services District
Consultant	GHD
Project	Highway Sewer Crossing Retrofit
Date	July 13, 2026

Pre-Bid Conference	1:30 P.M. on Wednesday, July 22, 2026, Non-Mandatory
Bid Opening	10:00 A.M. on Friday, August 21, 2026

No	Company Name / Information	Email
1.	Sacramento Builders' Exchange	RCheah@srbx.org
2.	Humboldt Builders' Exchange	hbe-info@humbx.com
3.	North Coast Builders' Exchange	planroom@ncbeonline.com
4.	Shasta Builders' Exchange	planroom@shastabe.com
5.	Medford Builders' Exchange	planroom@medfordbuilders.com
6.	Valley Contractors' Exchange Attn: Elizabeth Carter	Elizabeth@vceonline.com
7.	GR Sundberg	grs@grsinc.biz Casey@grsinc.biz ron@grsinc.biz
8.	Wahlund Construction, Inc. Robert W. Crittenden	Ryan@wahlcon.com bob@wahlcon.com bids@wahlcon.com
9.	Hooven & Co David Hooven	david@hoovenco.com
10.	Golden State Boring Jeff Johnson	Jeff@goldenstateboring.com
11.	California Auger Boring Bill Hunt Zack Poirier	Bill@calaugerboring.com Zack@calboring.com
12.	Allstate Boring Brian Sherrell	bsherrel1@gmail.com
13.	Boring Contractors Tim Cohn	tim@boringcontractors.com

No	Company Name / Information	Email
14.		
15.		
NOTE: This Planholders List includes only companies that received Contract Documents directly from the Owner or Owner's Representative. This list does not include planholders who received Contract Documents from third-party distributions, such as Builders Exchanges.		